

Turnpike ITS Design Guidance

Fiber Optic Cable, Conduit, and Connections

Fiber Optic Cable:

- Coordinate with the Turnpike Specifications Office to develop Section 102 Modified Special Provision (MSP) with the following requirements:
 - For device downtime:
 - Limit WWVDS downtime to overnight during ramp closure and testing
 - Limit CCTV downtime to 24 hours
 - Limit MVDS and VDS-AVI downtime to 48 hours
 - Limit HAR, RWIS downtime to 2 weeks
 - Provide a Method of Procedure (MOP) for the Turnpike's review and approval. Submit MOP a minimum of 14 days prior to outage request. The procedure shall include but not limited to cut-over plan, sequence of steps, field procedures, anticipated outage times, and any other necessary communications.
 - After the MOP is approved, provide the following notifications to the TMC at (407) 264-3363, ITS team at (954) 934-1400 & SunWatch at (877) 786-3375.
 - 48-hour advance request of the intended service disruption.
 - On the day of approved service disruption.
 - The following information shall be included when notification is provided:
 - Project FPID and Contract no:
 - Outage request contact name:
 - Caller call back name/cell #:
 - Planned date:
 - Planned date #2:
 - Planned start time:
 - Planned stop time:
 - Reason:
 - Prime contractor and cell #:
 - ITS subcontractor and cell #:
 - Splice subcontractor and cell #:
 - Location Mile Post (MP) and facility:
 - Affected Devices:
 - Proposed work requiring communication outages must be performed between 10:00 pm and 5:00 am.
- Ensure the design adheres to the above downtime requirements and make provisions accordingly in the plans.
- When terminating the backbone fiber optic cable within a Hub building, terminate all fibers within the Hub building rack.
- When relocating fiber optic backbone conduit, replace entire permanent fiber optic backbone between existing butt splices and/or minimum one mile of continuous fiber optic cable between butt splices.

Fiber Optic Route Marker:

- Place markers at a maximum spacing of 1000 feet.
- Label on the fiber route marker should include the following:

BEFORE DIGGING IN THIS AREA CALL
Florida's Turnpike Enterprise
954-934-1400
AND
SUNSHINE ONE CALL
1-800-432-4770

Conduit Infrastructure:

- Include a minimum of three 2-inch conduits for the ITS backbone fiber optic conduit system utilizing color scheme as described below:
 - Orange without stripes (backbone fiber optic cable)
 - Orange with white stripes (tone wire)
 - Orange with green stripes (spare)
- Include three 2-inch conduits for ITS lateral fiber conduits utilizing color scheme as described below. Provide lateral fiber optic cable and tone wire in separate designated conduits.
 - Orange without stripes (lateral fiber optic cable);
 - Orange with white stripes (tone wire); and
 - Orange with green stripes (spare).
- For conduits that require stripes, include three equally spaced longitudinal stripes of sufficient width and color intensity which are easily distinguished.
- Provide backbone and lateral fiber optic cable and tone wire in separate designated conduits.
- Include a minimum of one 2-inch conduit utilizing red colored (without stripes) conduit for the electrical conduit system.
- Use directional bore installation method for arterial and canal conduit crossings. If directional bore conduit installation is constrained, coordinate options with Turnpike ITS design.
- Include conduit casing (outerduct) of adequate size when conduits are installed under large water bodies such as canals etc.
- Include only one fiber cable in each conduit and avoid collocation of fiber cables inside the same conduit.

Splices, Terminations, and Connection Hardware

- Assign the backbone fiber optic cable buffers based on the following functionalities:
 - Blue and Green buffers → ITS Layer 3 Communications
 - Orange buffer → ITS Distribution
 - Red and Black buffers → Tolls

- Rest of the buffers → Reserved for other functionalities
- Allocate Orange buffer fibers to respective ITS device(s) based on the following:

| ITS Device Fiber Allocation | | |
|-----------------------------|---|--|
| Orange Buffer Fibers | ITS Device Type | Fiber Allocation Spacing |
| 1 | CCTV and Collocated Devices → | Stagger between fiber pairs for each adjacent CCTV |
| 2 | | |
| 3 | DMS and Collocated Devices → | Stagger between fiber pairs for each adjacent DMS |
| 4 | | |
| 5 | MVDS Generator Bluetooth AVI Wrong Way Detection | Alternate Between Fiber Pair |
| 6 | | |
| 7 | | |
| 8 | | |
| 9 | | |
| 10 | | |
| 11 | | |
| 12 | | |

- Coordinate fiber assignments with the Turnpike ITS and Network Administrator prior to the Phase III submittal.